

## **51<sup>st</sup> Street Infrastructure Project – Update**

Work is now underway in all areas of 51<sup>st</sup> Street. The construction company has provided the following tentative work schedule for the two blocks north of 54<sup>th</sup> Avenue:

*June 5 -16 Trenching operations will allow water main removal and replacement. New connections will be implemented. Operations will work within trench limits. A second series of trenching operations will take place for the sanitary sewer connections. Removal, replacement, and installation of the new connections will take place within trench limits. Temporary water services will start to be removed after pressure testing, and cleansing of all new systems has been tested and results forwarded to the Town and Engineer.*

*June 16-20 Road work to replace the subgrade materials as necessary, compact, add granular aggregates, and complete the subgrade operations. Gravel approaches will be left in place for access until the concrete prep work has begun.*

*July 27- August 24 Collins Concrete will now have better access to start the sidewalk, curb, and concrete work designed into this project. Concrete operations will be completed and during this time no traffic will be allowed on the finished work. Parking will be available on the street beside the curb. After the concrete has sufficiently cured the road subgrade and asphalt preparation will begin.*

Work between 51<sup>st</sup> Avenue and 54<sup>th</sup> Avenue is progressing. The sidewalk and curb has been placed and pavement will begin shortly. Once the pavement is in the boulevards will be landscaped.

If you have any questions or concerns about this infrastructure project, please contact the Town office at 403-882-3215.